



CLEAR WATER ALABAMA | SEPTEMBER 24<sup>th</sup>, 2025

# STORMWATER RESEARCH FACILITY UPDATES

MICHAEL A. PEREZ<sup>PHD, PE, CPESC</sup>



AUBURN  
STORMWATER

# AUBURN UNIVERSITY STORMWATER RESEARCH FACILITY



AUBURN  
STORMWATER




AUBURN  
ENGINEERING



# STORMWATER RESEARCH FACILITY

[in au-stormwater](#) [@StormwaterAU](#) [Auburn Stormwater](#) [stormwater.auburn.edu](#)



**ALDOT**  
Alabama Department of Transportation

**ADDEM**  
Alabama Department of Environmental Management

**NEBRASKA**  
Good Life. Great Journey.  
DEPARTMENT OF TRANSPORTATION

**IOWA DOT**  
SMARTER | SIMPLER | CUSTOMER DRIVEN

**dot**  
transportation.ohio.gov

U.S. Department of Transportation  
Federal Highway Administration


**NCHRP**

**EPA**

**USDA** United States Department of Agriculture

**USGS**  
science for a changing world

# FROM RESEARCH TO IMPLEMENTATION





# EVALUATION OF NDOT'S CONSTRUCTION STORMWATER DETENTION MEASURES USING FULL-SCALE TECHNIQUES



Auburn University – Stormwater Research Facility



AUBURN  
UNIVERSITY

NEBRASKA  
DEPARTMENT OF TRANSPORTATION

# NDOT DETENTION BASED PRACTICES

Practice	Description	Drainage Area	Sizing	Dewatering Mechanism
<b>Silt Trap</b>	Excavated ditch across the path of water to form ponding area, often includes silt check	< 1 ac	1 ft deep by 6 ft wide	None
<b>Sediment Trap</b>	Excavation with stabilized embankment	≤ 5 ac	134 yd <sup>3</sup> /ac typ. 67 yd <sup>3</sup> /ac min. 2:1 min. L:W	Riprap spillway w/weir height of 1 ft and length depending on drainage area
<b>Sediment Basin</b>	Excavation or embankment across a drainage way	> 5 ac	Vol. equivalent to the local 2-yr, 24-hr storm or 3,600 ft <sup>3</sup> /ac	Emergency spillway and dewatering device that pulls from the top of impoundment

# BACKGROUND



**Detention measures capture sediment by impounding runoff and facilitate settling.**

# PROBLEM STATEMENT




**NDOT detention measures have not been scientifically evaluated. Opportunities exist to enhance performance and design guidance.**

# RESEARCH OBJECTIVES



- **Develop full-scale testing methodology for performance comparison of detention practices**
- **Evaluate detention practices and modified installations through full-scale testing that mimics NDOT highway construction conditions**
- **Develop implementable design guidance**



# SILT TRAP



# SILT TRAP





WHEN REQUIRED A SILT TRAP (ST) SHALL BE EXCAVATED TO THE WIDTH OF THE DITCH AND NO DIRECT PAYMENT WILL BE MADE.

SECTION A-A



# DESIGN EXPERIMENTAL DETENTION MEASURES AND DEVELOP FULL-SCALE TESTING METHODOLOGY



Factors	Loess Hills	Loess Hills & Loess and Glacial Drift
avg K	0.375	0.357
avg P (in)	2.823	2.737
avg CN	88.125	86.680

# FULL-SCALE TESTING METHODOLOGY

Loess Hills & Loess and Glacial Drift	Drainage Area (ac)	Total Volume for Peak 30 min (ft <sup>3</sup> )	Peak Flow (cfs)	Average Flow for Peak 30 min (cfs)	Sediment Yield for Peak 30 min (lbs)	
	0.50	841	0.97	0.47	1,184	→ Silt Trap
	1.00	1,682	1.94	0.93	1,470	→ Sediment Trap

Per Test	Silt Trap	Sediment Trap
Drainage Area (ac)	0.5	1.0
Avg Flow Rate (cfs)	0.5	1.0
Sediment Load (lb)	1,100	1,470

# FULL-SCALE TESTING METHODOLOGY



**Sample Collection –  
Water Quality**



**Sediment Introduction –  
NE Condition Simulation**



**Test Apparatus – Flow  
& Sediment Regulation**

An aerial photograph of a construction site. At the top, a large, muddy pond is visible. Below it, a long, narrow channel has been excavated through the site. To the left of the channel, there are several rectangular structures covered with blue tarps. In the center, there is a pile of white material, possibly gravel or sand. To the right, there are several rectangular concrete slabs laid out on the ground. The site is surrounded by trees and a road is visible at the bottom. Two yellow arrows point from the text labels to the channel. One arrow starts from the 'SILT TRAP CHANNEL' label and points to the upper part of the channel. The other arrow starts from the 'SEDIMENT TRAP CHANNEL' label and points to the lower part of the channel.

**SILT TRAP  
CHANNEL**

**SEDIMENT  
TRAP  
CHANNEL**



# CONSTRUCTION OF DETENTION MEASURES








# SUMMARY OF TESTING



I-5: Silt Trap MFE-I and Sediment Trap MFE-I Combination → L1 L2 L3

# FULL-SCALE TESTING

- **Silt Trap: standard installations tested with back-to-back simulated runoff events to simulate filling and dewatering**



- **Results of standard testing will lead to development of modifications**
- **Develop and test Most Feasible and Effective - Installations (MFE-I)**

# NE STANDARD SILT TRAP





# EXCELSIOR WATTLE







# HIGH POROSITY SILT FENCE





# LOW POROSITY SILT FENCE





# MODIFIED SILT FENCE





# UPSTREAM ROCK CHECK



# MODIFIED ROCK CHECK



# SLASH MULCH BERM






# EARTHEN BERM



# % SEDIMENT CAPTURE











# DATA ANALYSIS

## Data Collection Locations for a Silt Trap





1. Standard (Control)

2. Excelsior Wattle

3. High Porosity Silt Fence

4. Modified Silt Fence

5. Low Porosity Silt Fence


6. Upstream Rock Check

7. Modified Rock Check



8. Slash Mulch Berm

9. Earthen Berm

Inflow




# SEDIMENT TRAP





# SEDIMENT TRAP FULL-SCALE TESTING

- standard installations tested with back-to-back simulated runoff events to simulate filling & dewatering



- Results of standard testing will lead to development of modifications
- Develop and test Most Feasible and Effective – Installation (MFE-I)


# SEDIMENT TRAP TESTING PLAN

1. NE Standard Installation
2. Baffles to dissipate flow energy
3. Surface skimmer for dewatering
4. MFE-I
5. Combination of Silt Trap MFE-I & Sediment Trap MFE-I



# DATA ANALYSIS

## Data Collection Locations for a Sediment Trap



# SEDIMENT TRAP STANDARD



# SEDIMENT TRAP STANDARD







# 24 HOURS AFTER TEST



# SEDIMENT TRAP WITH BAFFLES






# SEDIMENT TRAP WITH BAFFLES





# Improving Rock Check Dams Through Full-Scale Testing

AUBURN UNIVERSITY – STORMWATER RESEARCH FACILITY



AUBURN  
UNIVERSITY

IOWA  
DOT


# BACKGROUND

- **Ditch checks used to pool flow and slow velocity**
  - Converts erosive super critical flow into sub-critical
  - Erosion and sediment control
- **Common ditch check practices:**
  - Wattles
  - Silt fence
  - Rock check dams
- **Rock check dams offer advantages such as being able to withstand high flows**



# BACKGROUND

L = The distance such that points A and B are of equal elevation.




- **Spacing guidance based on theoretical ponding length**
  - Top of downstream practice at same elevation of bottom of upstream practice
- **In practice, many ditch checks do not reach the theoretical impoundment length**
  - Leaves portions of the channel unprotected from erosive flows

# RESEARCH OBJECTIVES

- **Evaluate existing Iowa DOT rock check dam standard**
- **Develop & evaluate efficient and cost-effective rock check dam installation enhancements**


# TESTING REGIME



**30 min. test duration**

- **Low Flow (15 min): 0.85 ft<sup>3</sup>/s**
- **High Flow (15 min): 1.70 ft<sup>3</sup>/s**

# CHANNEL DESIGN



Rock Check Dam

Earthen Dam

- 3% Grade ->

200 ft

42.5 ft


10 ft

5 ft

3H:1V

3.5H:1V

# TEST APPARATUS




# HYDRAULIC TESTING




- **Measurements:**
  - **Flow depth & velocity at 3 locations at each cross-section**
  - **Location of hydraulic jump**
  - **Dewatering time**

# IOWA DOT STANDARD INSTALLATION



- **Class D Revetment**
  - **Top size of 250 lbs | Min. 50% over 90 lbs | Min. 90% over 5 lbs**
- **Geotextile underlay**
- **No overlay or choker stone**

# IOWA DOT STANDARD INSTALLATION



# EVALUATED INSTALLATIONS

- Iowa DOT standard installation
- 7 modified installations w/ adjusted components
  - Removal of excavation
  - Smaller gradation of rock
  - Geotextile overlay
  - Dewatering holes in geotextile overlay
  - Reduced bottom width perpendicular to flow



# EVALUATED MODIFICATIONS

- **M1: Iowa DOT standard w/o excavation**
- **M2: Iowa DOT standard w/ smaller rock gradation**
- **M3: M1 + geotextile overlay**
- **M4: M3 + dewatering holes in overlay**
- **M5: M3 w/ smaller rock gradation**
- **M6: M5 + dewatering holes in overlay**
- **M7: M6 w/ reduced profile**



# Hydraulic Testing Results


# STANDARD INSTALLATION



- **Impoundment:**
  - 0.85 cfs: 4.2 ft = 6% impoundment efficiency
  - 1.70 cfs: 5.9 ft = 9% impoundment efficiency
- **Only reduced flow velocity immediately upstream of installation**

# PERFORMANCE COMPARISON

## Check Dam



# INSTALLATION COMPARISON: 1.70 FT<sup>3</sup>/S

Installation	Modification(s)	Avg. Impoundment Length (ft)	Max. Impoundment Depth (ft)	Impoundment Length Efficiency (%)	Cross-sections w/ sub-critical flow	Approximate Material Cost
Standard	-	5.9	0.6	9%	1	\$673
M1	Installed on Grade	8.1	0.64	13%	1	\$424
M2	Smaller Rock Gradation	32.7	1.05	52%	4	\$539
M3	Geotextile Overlay	48.4	1.99	77%	12	\$516
M4	Dewatering Holes	51.4	2.09	82%	11	\$516
M5	Smaller Rock w/ Overlay	56.8	1.85	90%	11	\$433
M6	Smaller Rock w/ Dewatering Holes	55.3	1.83	88%	12	\$433
M7	M6 w/ Reduced Profile	57.5	1.85	90%	12	\$304

# HYDRAULIC TESTING CONCLUSIONS

- **Excavation beneath installation provides little benefit while increasing cost**
- **Smaller Iowa DOT erosion stone outperforms standard Class D Revetment**
- **Addition of a geotextile overlay is vital to ensure installation impound flow and protect channels from erosion**
- **Dewatering holes in geotextile overlays reduce dewatering times without adversely impacting performance**
- **Reducing the width of installation can reduce material cost without impacting performance**
- **Additional erosion control practices may be necessary if the soil of the channel is particularly erosive**
- **Highest-performing rock check dams did not protect the entire channel from erosive flows**

# HYDRAULIC TESTING CONCLUSIONS



**Installation with no excavation, smaller Iowa DOT erosion stone, geotextile overlay with dewatering holes, & a reduced width was chosen as the MFE-I**

A photograph of a sediment retention testing setup. In the foreground, a large volume of thick, reddish-brown sediment-laden water flows over a low wall of grey and tan rocks. The water is contained within a channel lined with black geomembrane. In the background, a blue pickup truck is parked on a grassy field. Several workers in safety gear are visible near a piece of machinery, possibly a generator or pump, which is connected to the testing apparatus. The overall scene is outdoors on a bright day.

# Sediment Retention Testing Results

# SEDIMENT-LADEN TESTING



**Standard**




**MFE-I**

- **9.4% sediment capture**
- **All immediately upstream of the installation**

- **72.4% sediment capture**
- **Visibly coarse material at the hydraulic jump**

# WATER QUALITY



# CONCLUSIONS

- Installation with no excavation, Iowa DOT erosion stone, geotextile overlay with dewatering holes, & a reduce width was chosen as the MFE-1
- Increased impoundment from 6 ft to 58 ft
- Increased sediment capture by 7.7x
- Reduced discharge turbidity
- \$840k material cost savings (2019-2023)

# RECOMMENDATIONS

- **Add geotextile overlay to facilitate impoundment**
- **Use smaller rock to increase performance, reduce cost, and ensure proper heights of installations**
- **Add dewatering holes to ensure impoundment does not remain for excessive periods**
- **Can remove excavation and reduce width to further decrease material costs**
- **Extend geotextile downstream to prevent erosion due to high flow velocities**
- **Use additional erosion control practices in channels with highly erosive soils**

NCHRP 24-52

# GUIDELINES FOR RESILIENT E&SC PRACTICES

NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM



AUBURN  
STORMWATER



FAGAN  
FAGAN CONSULTING LLC

# RESEARCH OBJECTIVE


**develop guidelines for selecting, placing, designing, & maintaining E&SC practices**

- **Acquire deeper insight into current & emerging techniques in designing E&SC practices**
- **Develop new design & installation methods & evaluate their performance against standard designs through full-scale testing**
- **Develop & disseminate guidelines for selecting, placing, designing, & maintaining E&SC practices**




**RISK:** potential for an unwanted outcome resulting from an incident, event, or occurrence, as determined by its likelihood and associated consequences




- 
- Resist hazards or withstand impacts from weather events and natural disasters
  - Reduce the magnitude or duration of impacts of a disruptive weather event or natural disaster
  - Have absorptive capacity, adaptive capacity, and recoverability to decrease project vulnerability to weather events or other natural disasters
  - The consideration of incorporating natural infrastructure.

**RESILIENCY:** a system's ability to anticipate, prepare for, or adapt to conditions or withstand, respond to, or recover rapidly from disruptions with minimal or acceptable performance loss

# FIVE PILLARS OF CONSTRUCTION STORMWATER MANAGEMENT




# PROJECT TASKS



- **Growing concern with plastic-based sediment barrier practices**
- **Can use non-structural or more sustainable practices to aid vegetated buffers in sediment capture**
  - **ECBs, natural silt fence materials, etc.**
  - **Will identify testable materials**
- **Some innovative/sustainable SBs have been evaluated**



# CURLEX SILTTRAP (AMERICAN EXCELSIOR)



# BIO SILT FENCE



# BIO SILT FENCE



- **Composed of shredded/chipped wood material**
- **Incorporates natural infrastructure by using a recycled waste material**
  - **Removes need for potentially plastic-based E&SC practices**



## PROJECT #2

# SLASH MULCH BERMS FOR INLET PROTECTION & DITCH CHECKS


- **Have shown to be effective through evaluations at the AU-SRF in sediment barrier applications**
  - **98.2% sediment capture**
- **Some agencies have specs for ditch check applications**
- **No research has been conducted in ditch check or inlet protection applications**





## PROJECT #8 SLOPE DRAINS


- **No existing publications on slope drain performance**
- **Full-scale installations with various configurations**
- **Evaluate installations, flow velocity, and flow bypass**
- **Develop guidelines, sizing tools**




# PROJECT #3

## SLOPE DRAINS


- Testing in 2 parts: inlet and outlet treatments
- Evaluate slope drains of different diameters with flow rates according to calculated capacity



J-Hook



Straight  
Pipe




Tee

- **CGP requires 50 ft buffers when within 50 ft of a WOTUS or equivalent sediment controls**
- **Lack of guidance on sediment removal capabilities**



- Past testing has shown soil type, vegetation density/type, and buffer width influence sediment capture
- 11,664 vegetated buffer configurations representative of Nebraska were modeled
  - Avg. sediment capture: 92.6%



- **USDA's RUSLE2**
- **Use methodology outlined in Roche et al., 2023**
- **Using factors representative of the entire U.S.**

The screenshot displays the RUSLE2 software interface with a 3D model of a slope on the left and configuration panels on the right. The 3D model shows a slope with a horizontal distance of 270 ft and a vertical drop of 289.0 ft. The slope is divided into two segments: a top segment (218 ft) and a bottom segment (50 ft).

**STEP 1: Choose location to set climate:**  
 Location: Nebraska\Lincoln county average (North Platte)

**STEP 2: Choose soil type:**

Segment	Seg length (horiz), ft	Soil
1	218	...dy silty clay loam, 2 to 6 percent slopes\Moody Silty clay loam 98%
2	50	...clay loam, terrace, 0 to 2 percent slopes\Moody Silty clay loam 98%

**STEP 3: Set slope topography:**

Segment	Slope length to bottom of seg (along slope), ft	Seg length (horiz), ft	Steepness, %	Total vert. drops, ft	Sediment delivery, t/ac/yr
1	239.0	218.0	45	98	320
2	289.0	49.98	1.00	99	23

**STEP 4: Select and modify management:**

Segment	Slope length to bottom of seg (horiz), ft	Management	Sed. delivery, t/ac/yr
1	220	Highly disturbed land\Construction With No Practices\bare cut slope, smooth	210
2	270	dense grass	23

**STEP 5: Set supporting practices:**  
 Contouring: default  
 Diversions, Terraces, Sediment Basins: (none)

**STEP 6: Set Sediment barrier system:**  
 Sediment barrier set: open

**Summary:**  
 Soil loss, t/ac/yr: 320  
 Soil loss erod. portion, t/ac/yr: 320  
 Sediment delivery, t/ac: 23

## PROJECT #5

# OPTIMIZATION OF CONSTRUCTION SCHEDULING AND LIMIT/DELAYING DISTURBANCE THROUGH REGIONAL AND SEASONAL ANALYSIS

- **Maximum permissible exposed acreage may be outlined**
- **Identical acreage can have vastly different soil losses and sediment loading based on location & time of year**



# INNOVATING WITH ELECTROFLOCCULATION



**FAGAN**  
FAGAN CONSULTING LLC




**FHWA**




**SBIR**  
America's Seed Fund

# The Electric Floc Generator


enhances BMP performance by up to 90%



Control



Treated



00:03:09:19




# STORMWATER IMPLEMENTATION

# ADEM




AUBURN  
STORMWATER



**Impaired Watersheds**

- Soughatchee Creek
- Parkerson Mill Creek
- Moores Mill Creek
- Halawakee Creek
- UT to Halawakee Creek
- 303(d) Waterbody
- TMDL Waterbody
- Waterbody

- Hickory Dickory Park
- Litter Boom Location (Auburn)
- Litter Boom Location (Opelika)



# HICKORY DICKORY PARK






















**Bioretention Cell**

**Berm + Channel**

**Butterfly Garden + Cisterns**

**Permeable Path**

**Access Road**

**Channel**

**Bioretention Cell**

**Bioretention Cell**

**Streambank Stabilization**



















# Part Shade BRC 3 - Plants to Order: 216

X	Scientific Name	Common Name	Count
Vn	<i>Viburnum nudum</i>	Possumhaw Viburnum / Smooth Witherod	2
I.ve	<i>Ilex verticillata</i>	Winterberry Holly	2
I.vi	<i>Itea virginica</i>	Virginia Sweetspire	3
Cf	<i>Calycanthus floridus</i>	Sweetshrub / Carolina Allspice	1
Po	<i>Physocarpus opulifolius</i>	Ninebark	3
Hd	<i>Hypericum densiflorum</i>	Bushy St. John's Wort	3
Cg	<i>Clinopodium georgianum</i>	Georgia Calamint	11


**Subtotal (Shrubs): 25**

Abbr.	Scientific Name	Common Name	Count
Cs	<i>Chasmanthium sessiliflorum</i>	Longleaf Woodoats	36
Carex	<i>Carex cherokeensis</i> / <i>Carex vulpinoidea</i>	Cherokee Sedge / Fox Sedge	11
Cb	<i>Carex blanda</i>	Eastern Woodland Sedge	40

**Subtotal (Grasses & Sedges): 87**

Abbr.	Scientific Name	Common Name	Count
Fv	<i>Fragaria virginiana</i>	Wild Strawberry	15
Pt	<i>Pycnanthemum tenuifolium</i>	Narrowleaf Mountain Mint	3
Z	<i>Zizia aurea</i>	Golden Alexander	31
At	<i>Amsonia tabernaemontana</i>	Eastern Bluestar	19
Pc	<i>Penstemon calycosus</i>	Calico Beardtongue	24
Chrys	<i>Chrysogonum virginianum</i>	Green-and-Gold	12

**Subtotal (Herbaceous Perennials): 104**





## BENEFITS OF RAINWATER HARVESTING

- Environmental benefit:
  - Reduces transfer of contaminants from urban environments to streams.
  - Combats erosion and downstream flooding.



**RAIN BARREL**  
WORKSHOP at Kiesel Park





**SAVE WATER**  
USE A RAIN BARREL



**SAVE WATER**  
USE A RAIN BARREL



**SAVE WATER**  
USE A RAIN BARREL



**SAVE WATER**  
USE A RAIN BARREL





# Elizabeth White's post



Elizabeth White

August 20





FREE Rain Barrels in Auburn!

This weekend at Kiesel Park, Auburn families can learn how to turn stormwater into savings — and take home a rain barrel worth nearly \$80... for FREE.



Billy Wilson, Mary Beth Sayre and 465 others

84 comments 96 shares



# SCOOP THE POOP



PROTECT OUR WATER  
PREVENT POLLUTION





# AU-SRF TRAINING EFFORTS



AUBURN  
STORMWATER

# DESIGNER CERTIFICATION



**ALDOT** **ADEM**

# HANDS-ON TRAINING



**USDA** **USDA**  
**Rural**  
**Development**

# INSTALLER CERTIFICATION



**U.S. Department of Transportation**  
**Federal Highway**  
**Administration**

# STORMWATER WEEK

May 12-14, 2026



**AUBURN**  
STORMWATER

**MATT WISENDEN**  
**MDW0113@AUBURN.EDU**

**IECA**   
International Erosion Control Association®  
Protecting Soil and Water Resources





# Installer Training

AUBURN UNIVERSITY  
STORMWATER RESEARCH FACILITY

May 12-13, 2026



This 1.5-day event offers classroom and hands-on training for installing construction site erosion and sediment control practices. **Earn 10 PDHs.**

**Learn More** >>>

[stormwater.auburn.edu](http://stormwater.auburn.edu)





# Field Day

AUBURN UNIVERSITY  
STORMWATER RESEARCH FACILITY

May 14, 2026

This field day provides hands-on training and demonstrations of erosion and sediment control practices, including installation techniques and flow testing. **Earn 6 PDHs.**

\* Sponsorship and Exhibitor Opportunities Available



**Learn More >>>**

[stormwater.auburn.edu](http://stormwater.auburn.edu)





 TIGERSTREAM WEBINAR No. 13

# High Definition Stream Survey (HDSS): Transforming Water Resource Management

Register online at: [aub.ie/tigerstream](http://aub.ie/tigerstream)  
or scan QR code

Sept. 30, 2025 • 11:00 CDT



AUBURN  
STORMWATER

PRESENTED BY



**Brett Connell, MS**

Co-Founder

Trutta Environmental Solutions



REGISTER



**MICHAEL A. PEREZ**

PH.D., PE, CPESC

**BRASFIELD & GORRIE ASSOCIATE  
PROFESSOR**



**WESLEY N. DONALD**

PH.D.

**RESEARCH ASSOCIATE**



**MATTHEW WISENDEN**

M.S.

**EDUCATION & OUTREACH  
PROGRAM MANAGER**



**JAYDEN SIGGERS**

**RESEARCH TECHNICIAN**



**GUY SAVAGE**

**RESEARCH TECHNICIAN**





# AUBURN STORMWATER

[STORMWATER.AUBURN.EDU](http://STORMWATER.AUBURN.EDU)

[MIKE.PEREZ@AUBURN.EDU](mailto:MIKE.PEREZ@AUBURN.EDU)

 [au-stormwater](#)

 [Auburn Stormwater](#)

